The decommissioning program of the Doel and Tihange NPPs

March 2023





This communication contains internal information and is strictly intended for staff working within BU Nuclear only. This is document and the information it contains must not be distributed, presented, shown or broadcasted externally without written consent of the Communication Department of the Business Unit Nuclear.

Timeline Doel and Tihange NPP production



* Intermediate agreement signed between ENGIE and the Belgian federal government for the extension of Doel 4 and Tihange 3 for 10 years



Transitioning from production to decommissioning

Based on Master Schedule V6.00 (01/03/2023)



* Intermediate agreement signed between ENGIE and the Belgian federal government for the extension of Doel 4 and Tihange 3 for 10 years

** Adjustments to the decommissioning schedule in case of an extension of Doel 4 and Tihange 3 for 10 years are based on provisional estimates Q1/2023.



THE DECOMMISSIONING OF

THE DOEL AND TIHANGE NUCLEAR POWER PLANTS

An exciting industrial challenge with a focus on safety and professionalism



Decommissioning a nuclear power plant: a new challenge for the operator



Planning, design, licencing, ...

Removal of the nuclear fuel and all loose radioactive materials

Removal of all radioactive components and materials

Decommissioning is part of the life cycle of a nuclear power plant. It includes all administrative and technical measures taken from the final shutdown decision to the release of the site for new industrial activities.



MATERIALS AND WASTE are treated on site in designated buildings.

OUR AMBITION: Maximum waste reduction and recycling of parts and materials.



Post-Operations



Dismantling



WASTE PROCESSING AND MANAGEMENT





Dismantling

Dismantling of the internal parts of the reactor vessel

- In the reactor/refueling pool underwater for ALARA (~ tens of Sv/h)
- Remote dismantling with mechanical cutting techniques
- Requires heavy preparation work: structural reinforcement of the dock, collection of machining materials, rotary table, customized manipulation tools





Dismantling the internal parts with band saw at Stade nuclear power station, Germany







Dismantling

Dismantling of the remaining contaminated systems in the controlled area

Decontamination and release of building structures and the site:

- Peeling concrete
- Removal of contaminated inserts (pipe penetrations, ventilation ducts, expansion joints, etc.)
- Cleaning / decontamination of all surfaces
- Complete mapping of the installation

Final phase of the Decommissioning

· Administrative release from nuclear control of the reactor







Complete mapping of the concrete structures



This can be a long and expensive operation (many measuring points, double checks by the authorities, etc.)

Demolition



Note: nuclear constraints may remain if there are other facilities on the site.

Electrabel



Waste Management





From p	oroducer	to	exit
--------	----------	----	------

Radioactive Waste		Radioactivity		
		Low	Medium	High
Half-Life	Short	Cat A		Cat C
	Long	Cat B		







Fuel cycle



Fuel cycle







loading into fuel containers

Fuel Containers :

Weight (empty): +/- 100 T

Double function : transport & storage Capacity of 24 to 37 spent fuel elements Height: 5,4 meters, diameter: 2,4 meters



temporary storage on site (+/-80 years)



government decision final disposal concept



Characteristics of a fuel container





Fuel building

- The concrete building provides additional radiological protection.
- The passive ventilation allows residual heat to be dissipated
- Withstands extreme outdoor temperatures due to climate changes





Every great story deserves a great endingm

Safe nuclear & conventional safety, for people & environment

Professional

well organized, effective, cost driven & on time – to be benchmark in decommissioning

Responsible adhering to regulations & ethics with respect for society







